



ADDENDUM NO. 1

April 30, 2026

**RE: Fishing Pier Temporary Repairs Pending Full Replacement
(ITB-BP-0-2026/JH) Bid opening date: May 28, 2026 @ 2:30PM**

**FROM: City of Sanibel
800 Dunlop Road
Sanibel, FL 33957**

TO: Prospective Bidders and Others Concerned

This addendum is hereby incorporated into the bid documents of the project referenced above. The following items are clarifications, corrections, additions, deletions, and/or revisions to and shall take precedence over the original document.

A. Questions and Answers

Question No. 1: Are the Unit of measure correct on the Bid Tabulation for line-item numbers 7 through 12?

Response No. 1: See revised bid tabulation for corrected units of measure for line-item numbers 7 through 12. (P – 3 REV)



CITY OF SANIBEL
FISHING PIER TEMPORARY REPAIRS
PENDING FULL REPLACEMENT

BID OPENING
 May 28, 2026 @ 2:30 P.M.

| PAY ITEMS | | | | | | |
|----------------------|----------|------|--|--------------------|-------------------------|-----------------------------|
| Item No. | Quantity | Unit | Description | Unit Price (Words) | Unit Price \$ (Figures) | Extended Price \$ (Figures) |
| 1 | 1 | LS | Mobilization/Demobilization (Max 5%) | | \$ | \$ |
| 2 | 664 | SF | Deck Demolition | | \$ | \$ |
| 3 | 398 | LF | Pressure Treated Lumber 3" x 12" 2.5 PCF CCA (Rough Cut) | | \$ | \$ |
| 4 | 104 | LF | Pressure Treated Lumber 3" x 16" 2.5 PCF CCA (Rough Cut) | | \$ | \$ |
| 5 | 427 | LF | 6" X 6" Posts/Piles 0.60 PCF ACQ (Dimensional) | | \$ | \$ |
| 6 | 872 | SF | Tandeck 2x6 Decking | | \$ | \$ |
| 7 | 465 | LF | Tandeck 2X8 Top Rail | | \$ | \$ |
| 8 | 342 | LF | Tandeck 2X6 Side Railing | | \$ | \$ |
| 9 | 1 | LS | Existing Railing Hardware Inspection & Tighten All Hardware | | \$ | \$ |
| 10 | 1 | LS | Existing Hardware Replacement | | \$ | \$ |
| 11 | 1 | LS | Materials (Fasteners, Straps, Bolts, Screws, etc.. - 316 Stainless Steel) | | \$ | \$ |
| 12 | 1 | LS | Owner's Contingency | | \$ 25,000.00 | \$ 25,000.00 |
| PROJECT TOTAL | | | | | | \$ |