

12924 49th St N

Clearwater, FL 33762

Phone: 727-436-5044 Fax: 727-436-5003

Estimate PO # TBD

Date

6/9/2025

Client: City of Sanibel President:

Project Manger: Holly Milbrandt Bret Sapp

Phone: 239-472-3700 Email: holly.milbrandt@mysanibel.com

Address: 800 Dunlop Road Sanibel, FI 33957

Project Name: Dinkins Bayou Maintenance Dredging

Description of work: Dinkins Bayou filled in from storm damage. Owner is pulling an emergency permit to restore it back to previous conditions. Permit #

Dredging Services: Mechanically and hydraulically dredge approximately 13,540 cy of maintenance dredging sediment. Unload barge at Henderson Road boat ramp. Load directly into water tight sealed dumptrucks and hauled to city's Wulfert Wastewater Treatment Plant(WWTP) for final dewatering.

Engineering/Permitting Services: Owner is pulling emergency permits.

Hauling Services: Bayside Dredging will haul the material to WWTP. Silt fence will be installed prior to any dumping. Once dewatered, Bayside Dredging will haul all the sediment off the island.

Additional comments/notes: If additional material is requested to be removed, costs are identified below. Line item 1 will be reduced to \$0.00 if the project timing is coordinated with the dredging of Wulfert Canal. Both projects must start at the same time for the credit.

Note Contract to follow upon agreement on scope of work and permits if necessary

Item	Description	Qty	Rate	Amount
1	Mobilization	1	\$45,000.00	\$45,000.00
2	Dredging Area 1 (CY)	2350	\$90.00	\$211,500.00
3	Dredging Area 2, 2A, and 3 (CY)	8341	\$100.00	\$834,100.00
4	Dredging Area 4 and 4A (CY)	2849	\$100.00	\$284,900.00
5	Hauling (CY) Haul to WWTP	13540	\$15.00	\$203,100.00
6	Hauling Sediment off Island(CY)	13540	\$15.00	\$203,100.00
7	Survey and Stakeout	1	\$40,000.00	\$40,000.00
			Total	\$1,821,700.00

If you have any questions, please contact Bret Sapp at 727-436-5044.

We appreciate the opportunity to provide this scope of services and look forward to working with you.

SCC131152825