



Proposal #90123

To (customer): Sanibel Police Dept I/T
Mailing address: 800 Dunlop Rd
City, State, Zip Sanibel, FL 33957
Phone:
Email:

Date: 9/30/2014
Job Location: Server room
Street Address 800 Dunlop Road
Street Address
City, State, Zip Sanibel, FL 33957

Florida Hydronic Solutions Inc. is pleased to submit a proposal for labor and materials to perform:

Mackenzie Hall

Scope of work

The removal of the 10 ton Aeon air conditioning unit and Two 4 ton Aeon 100% outside air units. Provide engineered drawings for this design build project. Install a new 10 ton Daikin roof top air conditioning unit and a new 5 ton Daikin Rebel 18 SEER 100% outside air unit.

Daikin Maverick Mod#MPS010B 10TON RTU

Daikin Rebel Mod#DPS005A 100% OAU

Mackenzie hall Inclusions:

- Design Build Engineered drawings
- Removal of the old Aeon equipment 1= ac unit and 2= 100% outside air units
- Reconfiguration of the ductwork to accommodate the new units.
- Re-use the existing grills and flex off branches
- Provide a crane for removal of old equipment and installation of the new roof top units
- Install 1 Daikin Packaged roof top air conditioner
- 1 Daikin Rebel 100% outside air Roof Top unit 18 SEER (Variable speed High Efficiency)
- All units will have coil coating for corrosion resistance
- New steel duct work 24 Gauge for Trunk lines
- Installation of Plasma air device in ductwork
- DDC controls with network interface cards. Allows remote access to system
- Factory start up

Exclusions:

- No overtime- all work during regular business hours

Warranty

Manufacturer to provide 1 year parts warranty and 5 year compressor

FHSI to provide a one year labor warranty during regular business hours.

Cost:

Labor \$ 5,985
Materials/ Equipment \$60,531

TOTAL \$66,516